



**MINIMUM EXCAVATION SIZE:
6'-0" x 6'-0" x DEPTH REQUIRED.**

■ ILLUSTRATION IS TYPICAL ONLY OF GENERAL SERIES CONFIGURATION: FOR SPECIFIC CONFIGURATION, CALL JENSEN PRECAST.

- (A) TOP SLAB WT.= 1,800 Lbs.
- (B) 66" BOTTOM SECTION WT.= 9,300 Lbs.
- (C) 16" x 30" x 4 1/2" KNOCKOUT- EACH SIDE
- (D) 12" DIA. SUMP KNOCKOUT
- (E) 36" DIA. OPENING. SEE COVER AND NECKING SECTION
- (F) PULL IRONS (FLUSH)

- DESIGN FOR H-20-44 BRIDGE LOADING.
- ASSEMBLY TO BE PLACED ON A 6" BASE OF CRUSHER RUN FOR EASE OF INSTALLATION AND EVEN LOAD DISTRIBUTION.
- MINIMUM HEADROOM IS 5'-6". ADDITIONAL DEPTHS ARE AVAILABLE BY EXTENSION SECTIONS.

4'-0" x 4'-0" x 5'-6" MANHOLE		JENSEN PRECAST
ORG. DWG. DATE 08-01-04	REV. DWG. DATE	
		44X SERIES