



MINIMUM EXCAVATION SIZE:  
8'-0" x 14'-0" x DEPTH REQUIRED.

■ ILLUSTRATION IS TYPICAL ONLY OF GENERAL SERIES CONFIGURATION: FOR SPECIFIC CONFIGURATION, CALL JENSEN PRECAST.

- (A) TOP SECTION WT.= 16,200 Lbs.
- (B) BOTTOM SECTION WT.= 17,000 Lbs.
- (C) SUMP - VARIOUS SIZES AVAILABLE
- (D) VENT KNOCKOUTS
- (E) FOR COVERS: SEE COVER AND NECKING SECTION.
- (F) TERMINATORS - VARIOUS SIZES AVAILABLE

■ DESIGN FOR H-20-44 BRIDGE LOADING.

■ ASSEMBLY TO BE PLACED ON A 6" BASE OF CRUSHER RUN FOR EASE OF INSTALLATION AND EVEN LOAD DISTRIBUTION.

<b>6'-0" x 12'-0" x 7'-0"</b> <b>MANHOLE / VAULT</b>		  <b>612 SERIES</b>
ORG. DWG. DATE <b>11-15-00</b>	REV. DWG. DATE	