



MINIMUM EXCAVATION SIZE:
9'-2" x 20'-2" x DEPTH REQUIRED.

■ ILLUSTRATION IS TYPICAL ONLY OF GENERAL SERIES CONFIGURATION; FOR SPECIFIC CONFIGURATION, CALL JENSEN PRECAST.

- (A) TOP SECTION WT.= 37,400 Lbs.
- (B) BOTTOM SECTION WT.= 36,000 Lbs.
- (C) SUMP - VARIOUS SIZES AVAILABLE
- (D) VENT KNOCKOUTS
- (E) FOR COVERS: SEE COVER AND NECKING SECTION.
- (F) TERMINATORS - VARIOUS SIZES AVAILABLE

■ DESIGN FOR H-20-44 BRIDGE LOADING.

■ ASSEMBLY TO BE PLACED ON A 6" BASE OF CRUSHER RUN FOR EASE OF INSTALLATION AND EVEN LOAD DISTRIBUTION.

7'-0" x 18'-0" x 8'-0" MANHOLE / VAULT		JENSEN PRECAST
ORG. DWG. DATE 08-01-04	REV. DWG. DATE	